

MUNICIPAL CORPORATION, HOSHIARPUR

Name of work:- **ROUGH COST ESTIMATE
ESTIMATE FOR DISMANTLING, SHORTENING OF HEIGHT
AND RE-ERECTION OF STREET LIGHT POLES AT
DIFFERENT PLACES OF CITY**

Justification and need of the project :- These poles are very high and out of the reach of vehicle used for the repair of street light points. For making repair of these streets light points more convenient, the poles need to be shortened. Hence this estimate has been prepared accordingly.

Location of work:- As mentioned in the title

Existing facility:- Higher street light points

Proposed facility:- Shorten the height of street light points

Design criteria:- As per requirement

Specifications:- CSR

Rates:- CSR/NS Rates

Amount of Est Rs lac:- **0.81**

Time limit:- One month

Source of funding:- Corporation Fund

Previous estimate if the work is done earlier:- It is the new estimate.No specific estimate has been prepared earlier.

Estimate has been prepared and submitted for according technical sanction and obtaining Administrative approval, please.

Ashu
Junior Engineer.

Submitted for according technical sanction and obtaining Administrative approval, please.

A. K. S.
13-2-17
Assistant Corporation Engineer.

Technical sanction is accorded. The quantities of the estimate taken are tentative which may vary at the time of execution and rates provided in the estimate are as per the market rates. Some items may also differ from the estimate at the time of execution as per site conditions which shall be paid as per overall less of tendered rates. Work shall be got executed as per actual requirement and shall be paid accordingly as per lowest competitive rate after calling tenders. Submitted for obtaining Administrative approval, please.

hjj 21.12 (31)
Pm 23-5-17
[Signature]
Commissioner, Municipal Corporation.

[Signature] 13.2.17
Corporation Engineer.

APPROVED VIDE RESOLUTION NO. _____ DATED. _____


MUNICIPAL CORPORATION, HOSHIARPUR


ROUGH COST ESTIMATE

ESTIMATE FOR DISMANTLING, SHORTENING OF HEIGHT AND RE-ERECTION OF STREET LIGHT POLES AT DIFFERENT PLACES OF CITY

Sr No	CSR Item	Description of Item	N	L	B	H	Contents	Unit	Rate	Per	CP %	Amount
1	NS	Dismantling of fittings	54				54	Nos	150.00	each	0	8100.00
2	33.33 iii	Labour for dismantling poles	9				9	no.	520.94	each	5	4922.88
3	33 xi1603.	Making of CC muff of overall size 450 mm dia 800 mm long with CC 1:2:4 as per CSR specifications	9				9	Nos	1603.90	Each	5	15156.86
4	33.24 c	Painting of pole as per CSR specifications	9				9	Nos	165.15	Each	5	1560.67
5	NS	Cutting of poles	9				9	Nos	400.00	each	0	3600.00
6	33.33 v	Erection of poles as per CSR specifications	9				9	Nos	1468.90	each	5	13881.11
7	NS	Re erection of fittings	54				54	Nos	150.00	each	0	8100.00
8	33.09 iii	Re erection of fittings	9	6	22		1188	mtr	20.58	each	5	25671.49
Total											80993.00	
Or say Rs											0.81	


 Corporation Engineer
 M.C.Hoshiarpur.


 Assistant Corporation Engineer
 M.C.Hoshiarpur.


 Junior Engineer
 M.C.Hoshiarpur.