

MUNICIPAL CORPORATION, HOSHIARPUR**ROUGH COST ESTIMATE****ESTIMATE FOR DE-SILTING OF NALLAHS AT DIFFERENT PLACES IN THE CITY, HOSHIARPUR**

Name of work:-

Justification and need of the project :-

Location of work:-

Existing facility:-

Proposed facility:-

Design criteria:-

Specifications:-

Rates:-

Amount of Est Rs :-

Time limit:-

Source of funding:-

Previous estimate if the work is done earlier:-

This estimate has been prepared as report received from sanitary branch.

As mentioned in estimate.

Requirement of silt clearance

De-silting of nallahs

As proposed in the estimate.

PWD.

CSR Rates


6.59

Six months

Corporation Fund

It is the new estimate.No specific estimate has been prepared earlier.

Estimate has been prepared and submitted for according technical sanction and obtaining Administrative approval, please.


 Junior Engineer.

Submitted for according technical sanction and obtaining Administrative approval, please.


 Assistant Corporation Engineer.

Technical sanction is accorded. The quantities of the estimate taken are tentative which may vary at the time of execution and rates provided in the estimate are as per the market rates. Some items may also differ from the estimate at the time of execution as per site conditions which shall be paid as per overall less of tendered rates. Work shall be got executed as per actual requirement and shall be paid accordingly as per lowest competitive rate after calling tenders. Submitted for obtaining Administrative approval, please.


 Corporation Engineer

11.517


 Commissioner, Municipal Corporation.

APPROVED VIDE RESOLUTION NO. _____ DATED. _____

MUNICIPAL CORPORATION, HOSHIARPUR**ROUGH COST ESTIMATE****ESTIMATE FOR DE-SILTING OF NALLAHS AT DIFFERENT PLACES IN THE CITY, HOSHIARPUR**

Sr No	CSR Item	Description of item	N	L	B	H	Contents	Unit	Rate	Per	CP %	Amount
1	6.1	De-silting of nallah at various places										
	a	as per CSR specifications										
		Piplanwala Left Side	1	800	4	3.00	9600	cft				
		Piplanwala Right Side	1	1000	2	2.50	5000	cft				
		Dagana Road	1	800	2	2.00	3200	cft				
		Officer Colony Singriwala	1	400	2	2.00	1600	cft				
		Petrol Pump to Niara Road	1	400	2	3.00	2400	cft				
		Bharwain Road	1	2000	3	2.50	15000	cft				
		Premgarh to Sutehri Khurd	1	2000	4	3.00	24000	cft				
		Shastri Nagar	1	1000	3	2.50	7500	cft				
		Purhian	2	1000	3	2.00	12000	cft				
		CIA Staff to Choe Band Road	1	500	4	3.00	6000	cft				
		Red Road to Choe Band	1	1000	4	3.00	12000	cft				
		Hariana Road	1	1000	4	3.00	12000	cft				
		Total				Total	110300	cft				
		or							28.17	cum	80	158371.00
	4.1-B	Loading/Unloading							26.60	cum	75	145390.49
	5.2-i	Carriage upto 2km							93.00	cum	20	348562.37

Total

652323.85

6523.24

Total

658847.09

or say Rs

6.59Assistant Corporation Engineer
M.C.Hoshiarpur.Corporation Engineer
M.C.Hoshiarpur.Junior Engineer
M.C.Hoshiarpur.